

# Brilliant

.....designed for ease and flexibility



## SA Group Metering



A pre-wired group metering solution for multiple tenancy sites.

- Designed for both single and multi-phase installations.
- Pre-wired solutions for multiple tenancy installations in all areas of South Australia.
- Pre-wired and ready to fit meter.
- Meter and consumer links.
- Suitable for up to 125A main switch (not supplied).
- Pre-labelled for SIR compliance.
- Ample DIN space.
- Lockable meter isolators.
- Consumer neutral and earth links.
- Front panel removal for easy cable access and mounting.
- Key lockable enclosure to SAPN requirements.
- Tenancy sub-main MCBs.
- Metal loadcentre integrated with lock-off devices for meter isolation and service protection.
- Manufactured from 1.0mm galvanised steel to Z275 or 316 stainless steel.



Providing a pre-wired solution for multiple tenancy installations in South Australia, the pre-wired group metering enclosures comply with SA Supply Authority rules and regulations.

